
Invitation for Quotation

Name of the Work: Dismantling and Reinstallation of Split AC.

Location: CIF 001 IIT Dharwad.

With reference to the aforementioned work, quotations are hereby invited for the said work. Interested vendors with experience in electrical works can submit their quotes (*as per Annexure-I*) on their official letterhead, duly attested, **in a sealed envelope via post or courier** to the following address:

To,
IPS Office (NE-113),
First Floor Admin Block,
Indian Institute of Technology Dharwad,
Permanent Campus, Chikmalligwad.
Dharwad-580011.

Deadline for Submission: 14/04/2025 up to 1300 hours.

NOTE: Any quotes received after 1300 hours on 14/04/2025 shall not be accepted.

Annexure-I

Bill of Quantities for Dismantling and Installation of AC in CIF 001					
Sl. No	Description	Unit	Quantity	Rate in ₹	Amount in ₹
1	Releasing charges for split type air conditioner for one indoor and one outdoor unit is to be up to 3.0 Ton split/cassette type A/C with allied works.	Each	18		
2	Installation charges for split type air conditioner with allied works for one indoor and one outdoor unit is to be mounted on suitable Angle Iron support up to 3.0 Ton split/cassette type A/C.	Each	18		
3	Supplying and installation of insulated refrigerant copper tubing of 5/8" and 3/8" with polythene foam insulation 3 core 80 stand copper wiring between indoor and outdoor unit Leak testing oil and gas charging for additional piping length of tube.				
	Split	m	94		
4	Supplying & filling refrigerant for air conditioning equipment's. Which includes the labour & Nitrogen gas for pressure and leak testing.	Per kg	27		
5	Supplying and commisioning of AC Remote	No	8		
6	Supply and installing following size of preforted Hot Dipped Galvanised iron cable tray (Galvanisation thickness not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with GI suspenders including GI bolts & nuts etc as required.				

	100 mm width X 50 mm depth X 1.6mm thickness	m	51		
7	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work all complete.	kg	325		
8	Supply and fixing of Indoor Stand Universal Air Conditioner Split Indoor Unit Hanging Plate	Pair	13		
9	Supplying heavy gauge PVC conduit pipe 20 dia 2 mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc , and fixing using inverted wood plugs in case of RCC ceiling and RCC wall/ stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.	m	52		
10	Miscellaneous items - Core cutting	LS	1		
TOTAL					
GST					
GRAND TOTAL					

NOTE: All the above line items of works shall be executed as per CPWD Specifications meeting the site requirements. The scope of Contractor shall be Installation Testing Commissioning and Handover.

(Sign and Seal of the bidder)