

Bill of Quantity for Networking Works at Academic Block 1 Room No 012 IIT Dharwad					
SI No	Description of Item	UoM	Qty	Rate ₹	Amount ₹
1	24 Port uplink 1G Supported 24 port Manageable switch with configuration and 5 years support	Nos	1		
2	Cat 6A Cables/boxes	MTS	400.00		
3	Back Box	MTS	20.00		
4	45x45 PVC trunking	MTS	50.00		
5	2 Inch Reinforced/Polymeried flexible pipes	MTS	15.00		
6	12 Core OFC cable	MTS	110.00		
7	Fibre Pitails	Nos	12.00		
8	Fibre Splicing	Nos	12.00		
9	Fibre Patch cards (SC to LC)	Nos	2.00		
10	Cable laying with reinforced flexible and PVC trunking and with ceiling/wall, field side termination and face plate fixing with numbering, rack side dressing, bunching, termination, testing, patch card labeling and network switch patching and dressing.	Lumsum	20.00		
TOTAL ₹					
GST ₹					
GRAND TOTAL ₹					