

IITDh/IPS/LPC/2025-26/061  
25<sup>th</sup> June 2025

**Invitation for Quotation**

**Name of the Work:** Construction of Cricket Practice Pitch.

**Location:** Temporary Playground IIT Dharwad.

With reference to the aforementioned work, quotations are hereby invited for the said work. Interested vendors with experience in said works can submit their quotes (*as per Annexure-I*) on their official letterhead, duly attested, **in a sealed envelope via post / courier** to the following address:

To,  
IPS Office (NE-113),  
First Floor Admin Block,  
Indian Institute of Technology Dharwad,  
Permanent Campus, Chikmalligwad.  
Dharwad-580011.

**Deadline for submission:** 09<sup>th</sup> July 2025 up to 1730 hours

**NOTE:** Any quotes received after 1730 hours on 09/07/2025 will not be accepted.

Sd/-  
Executive Engineer  
Indian Institute of Technology Dharwad

Annexure-I

Bill of Quantity for Construction of Cricket Practice Pitch at Temporary Ground of IIT Dharwad					
Sl No	Description of Item	UoM	Qty	Rate ₹	Amount ₹
1	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	Sqm	7.6		
2	Prvoviding and Fixing Wire mesh (rabbit) as approved by Engineer-in-charge	Sqm	81.25		
3	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads including screed finishing to the satisfaction of engineer-in-charge ; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. All works upto plinth level Concrete of M25 grade with minimum cement content of 330 kg /cum.	Cum	8.13		
4	Supplying and stacking at site. Good earth. [incl payment of royalty, a slip / reciept from ZP / PWD/ dept of zeology and minerals. If applicable, else a declaration may be provided]	Cum	47.97		
5	Lead/Carriage for Good earth. 2KM	Cum	31.98		

6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	Cum	79.95		
<b>TOTAL ₹</b>					
<b>GST ₹</b>					
<b>GRAND TOTAL ₹</b>					

(Contractors Sign and Seal)